

Pyramid Paving LLC

3468 S BOSTON RD
TROY, VA 22974-3828 USA
+14345290975
lauren@pyramidpavingllc.com



Estimate

ADDRESS
Mark Stanley

ESTIMATE 6533
DATE 05/07/2026
EXPIRATION DATE 06/05/2026

PROJECT NAME
155 Factory Mill Rd

SALES REP
Kenny

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
	Remove old asphalt, regrade, & Pave	We will start by taking the old asphalt up and getting back to the sub grade. All old asphalt will be placed on the land beside where the work is taking place. We will begin taking the old pipe out the ground and shaping the new ditch line for the new double well 15 inch pipe. We will place 80 ft of double wall pipe and begin shaping the new entrance in. Cut down the grass that is not needed as well the dirt and use what dirt we can then fill the rest in with 21A stone. We will go back 100 ft in the existing road. After pipes are placed and all grading is complete we will start paving 3.5 inches of BM-25 base mix compacted to 3 inches. After base is placed and cooled off we will begin paving 2 inches of SM9.5 topping mix compacted to 2 inches. Total area being graded and paved is 2,000 Sf	1	30,000.00	30,000.00
	Additional Info.	This quote is based on a liquid asphalt price not to exceed \$781.25/ton. Due to the volatility in the liquid asphalt market; the price will be based on the inflation of liquid asphalt per the VDOT Asphalt Index at the time of construction. Drainage will not be guaranteed on paved areas having 1% grade or less.	1	0.00	0.00

TOTAL

\$30,000.00